No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	(*b*) Roofing with reinforced cement concrete and brick terrace (R. C. C. to be of broken granite jelly 1 : 2 : 4) with $\frac{3}{8}$″ dia. reinforcement bars for spans less than 10 feet placed at $4\frac{1}{2}$″ apart centre to centre and with negative moment and distribution bars and 2″ cross and longitudinal joints and with 3″ layer of surki concrete and then 2″ of cement stone jelly concrete including two courses of flat tiles and $\frac{1}{2}$″ thick, top and ceiling plastered and white washing with coving as per design, etc., complete	Sqr.		17·06	
2	Providing and fixing granite cut stone pillars 1′×1′×$10\frac{1}{2}$′ including base and capitals as per design neatly dressed complete	Each		10	

M. A. RAMANUJAM,
Assistant Engineer.

HASSAN DIVISION.

Notification.

1. Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 26th February 1938, for constructing first floor to the Administration Block of Sri Chamarajendra Hospital at Hassan.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for constructing first floor to the Administration Block of Sri Chamarajendra Hospital, Hassan." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 450 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member therefor or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Hassan Division, Hassan, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of June 1938, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 500 which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Superintending Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Hassan Division, Hassan.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will be, however, considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

Abstract estimate for constructing first floor to the Administration Block of Sri Chamarajendra Hospital at Hassan (for two wings).

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Dismantling parapet walls, etc.		Lumpsum		30
2	Constructing the walls with burnt brick in lime mortar	C.ft.	0 5 6	3686	
3	Arch work, burnt brick in mortar	C.ft.	0 6 6	416	
4	Cement concrete slab below roofing (1 : 2 : 4) ..	C.ft.	1 0 0	138	
5	Teakwood doors with fully panelled $1\frac{3}{4}''$ thick shutters with Bombay brass fittings, etc., complete with necessary frames and with fanlights at top	S.ft.	2 4 0	418	
6	Teakwood windows with glazed shutters of $1\frac{1}{2}''$ thick inside and panelled shutters outside, $\frac{3}{4}''$ iron bars 4″ centre to centre and with Bombay brass fittings, etc., complete with necessary frames and with fanlights at top	Sq.ft.	2 8 0	507	
7	Providing and fixing R. S. girders of 14″×6″ of 46 lbs. (or any other size as may be necessary) including hoisting and fixing, etc., complete with a coat of anticorrosive paint ..	Cwt.	12 0 0	133	
8	Reinforced cement concrete terrace work with 5″ thick of R. C. slab 3″ brick concrete and 2 layers of flat tiles, finished to proper slope on top for drainage including top and bottom plastering	Sqrs.	80 0 0	29·06	
9	Plastering with lime mortar and rounding of corners	Sqrs.	4 0 0	93·5	
10	Flooring with 2″ thick cement concrete with $\frac{1}{2}''$ red cement plaster finish (without bottom lime concrete)	Sqrs.	20 0 0	25·46	
11	Band cornice work as per existing design ..	R.ft.	0 10 0	220	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
12	Parapet wall with burnt brick in mortar $4\frac{1}{2}'' \times$ average $1\frac{1}{2}'$ with base sides, etc., plastering and with copings and pillasters, etc., as per existing design	R.ft.	0 10 0	216	
13	Painting with two coats of silicate paints	Sqr.	5 0 0	21·66	

Abstract Notification, dated 24th January 1938.

Attention of the public is invited to the detailed notification calling for tenders for restoring Khanderi Tank of Chalya, Chennarayapatna Taluk, published in pages 123-125, Part VI of *Mysore Gazette*, dated 27th January 1938. The last date for receipt of tender is 14th February 1938.

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Abstract Notification, dated 24th January 1938.

The attention of the public is invited to the notification published in pages 138-139 of the *Mysore Gazette*, dated 27th January 1938, calling tenders for the work of constructing a "High Level Causeway at 4/8 of Mudigere-Belur Road and forming the deviation road approaches to the High Level Causeway."

The last date of receipt of tender in this office is 14th February 1938.

Abstract Notification, dated 24th January 1938.

The attention of the public is invited to the notification published in pages 140-141 of the *Mysore Gazette*, dated 27th January 1938, calling tenders for the work of constructing "Reinforced Concrete Bridge across Yeechalahalla in $\frac{7}{8}$ of Mudigere-Byduvalli Road."

The last date of receipt of tender in this office is 14th February 1938.

C. R. IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

No. T. C. 295—37-38, *dated* 19*th November* 1937.

Notice.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued, with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT STATIONERY DEPOT, BANGALORE.

Abstract Notification dated the 24th January 1938.

The attention of the public is invited to the detailed notification, dated the 24th January 1938, regarding the sale by public auction of certain unserviceable articles of the Stationery Depot, on Thursday, the 3rd March 1938 published on page 127 of Part VI of the *Mysore Gazette*, dated 27th January 1938.

B. SRINIVASA IYENGAR,
Superintendent.